Hippos (Sussita) Excavations 2013 – 14th Season Daily Log + Drawing

Date: <u>4 July 2013</u> Area: <u>NIP</u> Manager: <u>Schuler</u>

Squares	DH39 North	DI40 north	DH40 north	
Loci	2115	1243	1237	
Baskets	3149	3150		
Walls 1244, 1285, 2114,1946				
Floors 2116				

1. Continued work in the "gathering hall" (Squares DH40 south with the NW corner of DI39 and the

east edge of DG39) and DH39 North

- a. Goal = identify the south end of the Beta Building
- b. Basket = 3149
- c. Starting elevation = 128.13 (NE corner), 128.11 (SW corner), 128.14 (SE corner). 128.42 (step)
- d. Ending elevation = 127.97 (NW corner), 128.06 (east side of column)
- e. Soil = horizon C (white and chalky)
- f. Finished room except for final sweeping
- g. Discovered two limestone drums and a lintel stone in NW corner
- h. NW corner paving is poorer in quality and slightly sunken.
- i. Cleaned up W1285.
- j. Final sweeping and drawing remain to be done.
- k. Some walls will need to be lowered before the end of the season.
- I. Ceramic analysis
 - i. Mainly dating from 5AD
 - ii. Mainly dating to 7AD
 - iii. Stratigraphic context: South-West room (DG 39), under the L.2113
 - iv. Description: Several fragments of jars, basin rim and cooking pot rim
 - v. Indicative wares: Bet Shean jar

Item Number	755
Category	Architecture
Material	marble
Shape	square
State of	Nearly complete

Preservation Width Length DepthThickness Elevation From East From North To be Drawn Description	19.0 20.5 3.0 128.96 3.18 3.16 No fragment of an altar screen, cut, perhaps functioned as a sill for a window.
Item Number	756
Category	Architecture
Material	marble
Shape	column
State of	More than half
Preservation	
Width	21.0
Length	67.0
DepthThickness	22.0
Elevation	128.11
From East	2.9
From North	4.1
To be Drawn	Yes
Description	fragment of spiral fluted column in marble with square base
Item Number Category Material Shape State of Preservation Width Length DepthThickness Elevation From East From North To be Drawn Description	757 Architecture limestone column drum Nearly complete 36.0 33.0 36.0 128.11 2.4 4 No used as leg? for t able, found to east of fluted column
Item Number Category Material Shape State of Preservation Width Length DepthThickness	758 Architecture limestone drum Nearly complete 36.0 33.0 35.0

Elevation	128.11
From East	3
From North	3.85
To be Drawn	No
Description	worn column drum.
Item Number	759
Category	Architecture
Material	basalt
Shape	lintel stone
State of	Nearly complete
Preservation	1.0
Width	1.0
Length	1.0
DepthThickness	1.0
Elevation	128.11
From East	3
From North	3.5
To be Drawn	No
Description	in corner with two limestone drums and fluted column
Item Number Category Material Shape State of Preservation Width Length	760 Architecture basalt plain capital Perfect 1.0 1.0
DepthThickness	1.0
Elevation	1
From East	1
From North	1
To be Drawn	Yes
Description	likely a pilaster base for arch

- 2. Continued work in Square DI40 north.
 - a. Goal = identify the structure and function of Beta Building
 - b. Basket = 3150
 - c. Starting elevation = 129.25 (average west), 129.47 (average east)
 - d. Ending elevation = 129.16
 - e. Soil is Horizon B
 - f. Removed much rock and fill
 - g. Soil change toward the end of the day (entering L2101)
 - h. Two marble fragments (of a plate and a frieze) we're discovered next to the north wall.
 - i. Ceramic analysis

- i. Mainly dating from 6AD
- ii. Mainly dating to 8AD
- iii. Stratigraphic context: North-East room (DI 40)
- iv. Description: Mostly body shards of jars and cooking vessels made of brown-black


material

v. Indicative wares: Bet Shean jar rim

	7/0
Item Number	762
Category	marble
Material	marble
Shape	plate
State of	Fragment
Preservation	
Width	18.0
Length	12.0
DepthThickness	1.5
Elevation	129.26
From East	-0.4
From North	0.75
To be Drawn	No
Description	plate diameter?
-	
Item Number	763
Item Number	763 Architecture
Category	Architecture
Category Material	Architecture frieze frag
Category Material Shape	Architecture frieze frag frieze
Category Material Shape State of	Architecture frieze frag
Category Material Shape State of Preservation	Architecture frieze frag frieze Fragment
Category Material Shape State of Preservation Width	Architecture frieze frag frieze Fragment 14.5
Category Material Shape State of Preservation Width Length	Architecture frieze frag frieze Fragment 14.5 21.0
Category Material Shape State of Preservation Width Length DepthThickness	Architecture frieze frag frieze Fragment 14.5 21.0 7.5
Category Material Shape State of Preservation Width Length DepthThickness Elevation	Architecture frieze frag frieze Fragment 14.5 21.0 7.5 129.26
Category Material Shape State of Preservation Width Length DepthThickness Elevation From East	Architecture frieze frag frieze Fragment 14.5 21.0 7.5 129.26 -0.1
Category Material Shape State of Preservation Width Length DepthThickness Elevation From East From North	Architecture frieze frag frieze Fragment 14.5 21.0 7.5 129.26 -0.1 75
Category Material Shape State of Preservation Width Length DepthThickness Elevation From East	Architecture frieze frag frieze Fragment 14.5 21.0 7.5 129.26 -0.1

3. Opened DH40 north

- a. Goal = identify the structure and function of Beta Building
- b. Basket = none
- c. Starting elevation = 131.05
- d. Ending elevation = 131.01
- e. Identified seam in W1946 on the west exterior. W1946 forms a corner with W2114. The corner is stabilized by alternating headers and stretchers through the courses. The wall that continues to the north abuts W2114.



f. Cleared rubble from the top of the first course of W1946 north of W2114.